KADUR FOREST DIVISION, CHIKMAGALUR.

Notification dated the 13th June 1936.

Notice is hereby given that sealed tenders will be received at the Office of the District Forest Officer, Kadur Division, up to 4 P.M. on Monday the 29th June 1936 for the purchase of the exclusive right of collecting the Minor Forest Produce on all Government unoccupied lands, Amrit Mahal Kavals, State Forests, Reserved lands and plantations for two years from 1st July 1936 to 30th June 1938, in Chikmagalur Taluk.

2. For other particulars, please see the Notification No. D1—1209-35-36, dated the 4th May 1936 of the Chief Conservator of Forests in Mysore, Bangalore, published on pages 692-693, Part VI of the *Mysore Gazette*, dated the 14th May 1936.

A. V. KESAVIENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT

OFFICE OF THE EXECUTIVE ENGINEER, WATER SUPPLY DIVISION, BANGALORE.

Abstract Notification dated 5th June 1936.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, dated 11th June 1936, Part VI, page 843, calling for quotations for converting the open settling tank of 3½ million gallons capacity at Combined Jewell Filters, Bangalore, into a covered pure water reservoir by roofing and providing pillars, etc. The last date for the receipt of the tenders is hereby extended to 15th July 1936.

Abstract Notification dated 5th June 1936.

The attention of the public is invited to the *Mysore Gazette*, Part VI, pages 843-845, dated 11th June 1936, calling tenders for removing two miles of old C.I. Pipes of the 15" rising main from Tarabanahalli to Combined Jewell Filters. Last date of receipt of tender is 29th June 1936. Earnest money to be deposited is Rs. 350.

V. GANESHA IYER,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Abstract Notification dated the 6th June 1936.

Attention of the public is invited to the detailed Notification, calling for Tenders for converting an old ward in Krishnarajendra Hospital, Mysore, into a European Special Ward, published on pages 845-848, Part VI of the *Mysore Gazette*, dated 11th June 1936. The last date for receiving tenders is 24th June 1936, 12 Noon.

Abstract Notification dated the 6th June 1936.

Attention of the pulbic is invited to the detailed Notification, calling for Tenders for constructing a Kitchen Block in Krishnarajendra Hospital, Mysore, published on pages 848-851, Part VI of the *Mysore Gazette*, dated 11th June 1936. The last date for receiving tenders is 24th June 1936, 12 Noon.

S. RAMASWAMY,
Assistant Engineer.

HASSAN DIVISION.

Notification dated 12th June 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 27th June 1936 up to 3 P.M. for constructing a Porch in front of the Circuit House at Hassan. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Porch in front of the Circuit House at Hassan" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Estimate for constructing a Porch in front of the Circuit House at Hassan.

No.	Items of work	Quantity	Per	Rate	Cost
				Rs. a. p.	Rs. a. p.
1	Earthwork excavation for foundation ..	15	C.yd.	0 3 0	
2	Concrete in chunam mortar	110	C.ft.	0 4 0	
3	Size stone in chunam mortar	288	„	0 5 0	
4	Cut stone in mortar with cement pointing ..	123	„	0 10 0	
5	Providing and fixing cut stone pillars of 14″ diameter at bottom and 12″ diameter at top, including base and capital with fine dressing (10′ to 11′ height in all) ..	8	Each	75 0 0	
6	Providing and fixing Tata's tested rolled steel beams of 10″ ×4½″ of 25 lbs. with necessary clamps, etc., complete	15	Cwt.	12 0 0	
7	Boxing the girders above the portico ..	67	R.ft.	0 12 0	
8	Roofing with reinforced concrete terrace, including Cuppy concrete and two courses of flat tiles and plastering	4.29	Sqr.	80 0 0	
9	Plastering with composite mortar with the required beading alround	3.5	„	6 0 0	
10	Constructing plain cornice	142	R.ft.	0 8 0	
11	Constructing ballustrated parapet wall as per design to a height of 1½′	282	„	2 8 0	
12	Providing and fixing masonry ornamental finials	2	Each	4 0 0	
13	Providing and fixing pedement as per design in the centre of portico with a flag post ..	1	„	50 0 0	
14	Providing and fixing angle iron clamps with necessary strap iron fastenings in the pillars	10	„	8 0 0	
15	Providing and fixing asbestos sheets with angle iron frame and Teakwood beading and painting, etc., as per design ..	225	S.ft.	0 10 0	
16	Providing and fixing glazed sun shade with coloured ornamental thick glass with necessary iron and Teakwood frame works as per design	300	„	1 8 0	
17	Providing and fixing ornamental C.I. hand railings 2′ height in between pillars ..	66	R.ft.	2 0 0	
18	Removing old plaster in pillars and replastering the same with Shell lime	7.50	Sqr.	10 0 0	
19	Unforeseen charges including dismantling parapet walls and constructing steps, etc.	L.S.			

N. LAKSHMINARASIMHIAH,
Executive Engineer.